

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 130-40

LOCATION NE NE SW

SEC. 2 TWP. 10 RGE. 23

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Law _____

Operator Harry Gore Address Wichita, Kans

Field _____ County Graham

Total Depth 4286 Feet.

Plugging Contractor R & S Pipe Pulling Co

Plugging Contractor's License No. 1

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 178' circulated with cement - 5 1/2" at 4202'

with 150 sax cement behind - Lane Wells plugs at 4164' -

top perforations at 4128'.

Filled with sand to 4100' set 4 sax cement with dump bailer,

pulled 1115' 5 1/2" - mud to 175' set rock and 15 sax cement,

mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
10-19-53
OCT 19 1953

District Conservation Agent

Date 10-17-53

PLUGGING

SEC 2 T 10 R 23w CONSERVATION DIVISION
Wichita, Kansas
OR PAGE 120 LINE 40