

15-065-03060-0000

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 54-8  
LOCATION SW SW NE  
SEC. 8 TWP. 10 RGE. 23

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Law

Operator Amerada Pet Co Address Box 2040 Tulsa, Okla

Field \_\_\_\_\_ County Graham

Total Depth 3948 Feet.

Plugging Contractor Forbes Casing Pulling & Globe Cementing Co

Plugging Contractor's License No. 49

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 245' circulated with cement - 5 1/2" 3948' with 700 sax cement behind.

P.B. to 3876', perforated 3864' - Filled hole with sand to 3850', set 4 sax cement with dump bailer, started 517' 5 1/2" and circulated hole with heavy mud at 500', (63 sax Gel through 5 1/2" ) - displaced 20 sax cement through 5 1/2" at 500', heavy mud to 240', displaced 20 sax cement through 5 1/2" at 240', heavy mud to 35', set bridge and 10 sax cement to bottom cellar - Mudding and cementing by Globe Cementing Co.

*Edward L. ...*

District Conservation Agent

Date 12-3-57

*RCWD  
12-09-57*

PLUGGING  
FILE SEC. 8 T. 10 R. 23  
BOOK PAGE 54 LINE 8