

15-005-19219-0000 R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,
Complete Address Box #352, Russell, Kansas. 67665
Lease Name Dietz Waterflood Well No. B-4
Location SE-NE-NW Sec. 8 Twp. 10 Rge. (E) (W) 23
County Graham Total Depth 3960'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Ralph Comstock Casing Pulling, Incorporated,
Address 320 So. Park, Stafford, Kansas. License No. 490
Operation Completed: Hour 11:00 AM Day 5 Month 6 Year 1971

The above well was plugged as follows:

185'--8 5/8" Surface casing, cement circulated.
3958'--5 1/2" casing cemented on bottom. No plug back nor perforations indicated.
Pushed plug to 3700', sanded well back to 3675' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing (884') and squeezed well with initially 5 sacks hulls and followed
with 15 sacks gel then 100 Sx. cement, followed with 15 sacks gel and finally 50 Sx.
cement. Maximum pump-in pressure-250#. Final shut-in pressure-150#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 6-14-71
INV. NO. 3863-W