

15-065-03063-0081  
Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,  
Complete Address Box #352, Russell, Kansas.  
Lease Name Dietz Waterflood Well No. 2-R (Dietz B-2)  
Location NW-SE-NW Sec. 8 Twp. 10 Rge. (E) (W) 23  
County Graham Total Depth 3963'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Ralph Comstock Casing Pulling, Incorporated,  
Address 320 So. Park, Stafford, Kansas. License No. 490  
Operation Completed: Hour 12:45 PM Day 3 Month 6 Year 1971

The above well was plugged as follows:

186'--8 5/8" Surface casing, cement circulated.  
3950'--5 1/2" casing cemented on bottom with 150 Sx. No plug back nor perforations indicated.

Squeezed well with 5 sacks hulls and followed with 20 Sx. cement then 27 sacks gel and followed with 40 Sx. cement then 5 sacks gel and finally 30 Sx. cement. Maximum pump-in pressure 500#. Final shut-in pressure-150#. (Mudding and cementing by Allied Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 6-10-71  
INV. NO. 3835-W