

9

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Dietz Waterflood Well No. 1 (Dietz #B-1)

Location SE-SE-NW Sec. 8 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3995'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ralph Comstock Casing Pulling, Incorporated,

Address 320 South Park, Stafford, Kansas. License No. 490

Operation Completed: Hour 12:00 M Day 3 Month 6 Year 1971

The above well was plugged as follows:

186'--8 5/8" Surface casing, cement circulated with 135 Sx.

3994'--5 1/2" production casing cemented on bottom with 100 Sx. Well plugged back to 3965'. Top perforations @ 3940'.

Pushed plug to 3700', sanded well back from 3700' to 3675' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed with 100 Sx. cement from 1125' to 800' then 15 sacks gel from 800' to 200' and finally 70 Sx. cement from 200' to bottom of cellar. Maximum pump-in pressure-200#. Final shut-in pressure-100#. (Mudding and cementing by Allied Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 6-10-71

INV. NO. 3837-W