

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
NOV 21 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name March Drilling Company, Incorporated,

Complete Address: P.O. Box #463, Hutchinson, Kansas.

Lease Name Dietz Well No. 1

Location CW/2-W/2-NW/4 Sec. 8 Twp. 10 Rge. (E) (W)23

County Graham Total Depth 4000

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Halliburton Company,

Address: Hill City, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 5:30PM Day 11 Month 11 Year 1966

The Above well was plugged as follows:

204'--8 5/8" Surface pipe, cement circulated with 160 Sx.  
4000'--5 1/4" casing cemented on bottom. 2" tubing in well.

Displaced 10 Sx. heavy gel mud and 25 Sx. cement on bottom thru 2" tubing.  
Pulled 5 1/2" tubing to 700' and circulated heavy gel mud then displaced 10  
Sx. cement thru tubing. Pulled tubing to 210' and displaced 10 Sx. cement  
thru Tubing. Pulled tubing, set bridge @ 35' and 5 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 11/21/66  
INV. NO. 4314-4