

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1962
11-13-62
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sierra Pet Co

Complete Address: 208 Pet Bldg Wichita, Kansas

Lease Name Dietz Well No. 1 3-C

Location NE NE SW Sec. 8 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3990

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: wash down

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 9AM Day 11 Month 11 Year 62

The Above well was plugged as follows:

8 5/8" 199' circulated with cement - 5 1/2" 3982' with 150 sax cement.
filled with sand to 3970', set 4 sax cement with dump bailer - pulled
1235' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at
550', displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180',
displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', cement
35' to bottom cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Eaton Stealy*
Well Plugging Supervisor

DATE 11/13/62
6063-43
INV. NO. ~~3000~~