

15-065-03062-0000



Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Dietz Waterflood Well No. 2 (Dietz #2)

Location N/2-N/2-SW Sec. 8 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3995'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Ralph Comstock Casing Pulling, Incorporated,

Address 320 South Park, Stafford, Kans. License No. 490

Operation Completed: Hour 1:45 PM Day 1 Month 6 Year 1971

The above well was plugged as follows:

180'--8 5/8" Surface casing, cement circulated.
3995'--5 1/2" casing cemented on bottom. No plug back indicated, top perforation @
3900'.

Pushed plug to 3700', sanded back from 3700' to 3675' and set 5 Sx. cement with dump
bailer. Pulled 5 1/2" casing (750') and squeezed well with 4 sacks hulls and 15 sacks
gel and followed with 100 Sx. cement from 1050' to 725' then 13 sacks gel from 725'
to 200' and finally 70 Sx. cement from 200' to bottom of cellar. Maximum pump-in
pressure--400#. Final shut-in pressure--200#. (Mudding and cementing by Globe).

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Diebold
Well Plugging Supervisor

INVOICED

DATE 6-10-71

INV. NO. 3834-W