

6-11-87

6 070563

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,384-0006 22
SE NE NW, SEC. 3, T. 10 S, R. 33 W
4290 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5474
Operator: Northern Lights Oil Co.
Name & Address: 212 N. Market #400
Wichita, Kansas 67202
John W. Sutherland, Jr.

Lease Name Hindman Well # 1
County Graham 123.50
Well Total Depth 3800 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____
Address Box 69 Hays, Kansas 67601

Company to plug at: Hour: 12:30 PM Day: 11 Month: June Year: 19 87

Plugging proposal received from Arnie Hess

(company name) Mallard Drilling Inc. (phone) 316-263-1008

were: 8 5/8" - 254 ft. S.P. cwc w/1500 sks 60/40 Poz. 3% Gel, 2% Ca Cl. By Allied Cmt.
Proposal order 200 sks 60/40 Pozmix 6% Gel #% Ca Cl 1 sk Celloflake and 8 5/8" plug.

Spot with drill stem, recondition hole, heavy mud betwween all plugs. No circulation
problems, Elv. 2314, Anhy 1821, Mud condition, 40 Vis. 9.4 weight, 9.6 water loss, spot
and displace w/mud, 25 sks at 1840', 100 sks w/1 sk Celloflake at 990 ft. 40 sks at 300'
10 sks at 40', 15 sks rat hole, 10 sks mouse hole. (Cir)

L.K.C. well.

Plugging Proposal Received by Marion Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 2:45PM Day: 11th Month: June Year: 19 87

ACTUAL PLUGGING REPORT _____ Ordered 200 sks 60/40 Pozmix 6% Gel, 3% Ca Cl.
and 8 5/8" plug.

Spotted with drill stem with heavy mud betwween all plugs.
1st plug at 1840 ft. w/25 sks. cmt, 2nd plug at 990 ft. w/100 sks cmt. w/1 Celloflake.
3rd plug at 300 ft. w/40 sks cmt, 4th plug Hulls, plug at 40' w/10 sks cmt.
15 sks in rat hole (circulate) 10 sks in mouse hole (circulate).

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas
JUN 23 1987

Remarks: By B. J. Titan, Hays, Kansas
(if additional description is necessary, use BACK of this form)

INVOICED

DATE 6-24-87

INV. NO. 17311

Signed Marion Schmidt
(TECHNICIAN)
Marion J. Schmidt