

9-2 15-065-01820-0000

4-031856

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1954

NE SW SW /4 SEC. 36, 10 S, 21 W
990 feet from S section line
4290 feet from E section line

Operator license# 6568 Lease Schneider well # A 5

Operator: Kaiser-Francis Oil Company County Graham

Address: P.O. Box 21468 Well total depth 3677 feet ^{119.50}
Tulsa, OK 74121-1468 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 204 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Hembre Well Service License# 6907

Address: Ness City, Kansas 67560

Company to plug at: Hour: P.M. Day: 2 Month: September Year: 93

Plugging proposal received from: Gordon

Company: Kaiser-Francis Oil Company Phone: _____

Were: Order 350 sxs. 65/35 pozmix - 10% gel. - 500# hulls.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 1:30P.M., Day: 2, Month: September, Year: 93

Actual plugging report: 8 5/8" set @ 204' w/125 sxs. 5 1/2" set @ 3668'
w/125 sxs. O.H. 3668' - 3677'. Squeezed @ 1212' w/100 sxs. Casing leaks
C.H. to anhydrite. Shot @ 2120'. Ran tubing to 2500'. Pump 50 sxs.
cement blend, pull to 1350' circulate cement to surface. Squeezed 5 1/2"
with total 200 sxs. cement blend w/200# hulls mixed in to max. P.S.I.
500#. Close in P.S.I. 500#. Squeezed 8 5/8" with 50 sxs. cement blend
to max. P.S.I. 500#. Close in P.S.I. 150#. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC , NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ Elevation: _____ GL _____

I did[] / did not[] observe the plugging.

Carl Goodrow
(agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1993

Form CP-2/3
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 9-28-93
INV. NO. 38805