

4- 031768

10-6  
15-065-00453-0000  
223  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1954

NW NE SW /4 SEC. 36, 10 S, 21 W  
2310 feet from S section line  
3630 feet from E section line

Operator license# 6568

Lease Schneider well # A-2

Operator: Kaiser-Francis Oil Company

County Graham

Address: Box 21468  
Tulsa, Oklahoma 74121-1468

Well total depth 3714 feet <sup>120.71</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 209 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 6 Month: October Year: 92

Plugging proposal received from: John Glenn

Company: Kaiser-Francis Oil Company Phone:                     

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Hole open to perf.  
Pulled rods and tubing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 10:40A.M., Day: 6, Month: October, Year: 92

Actual plugging report: 8 5/8" set @ 209' w/125 sx. cwc. 5 1/2" set @  
3685' w/125 sx. Squeezes @ 1625' w/300 sx. - @ 924' w/200 sx.  
Protected anhy. and dakota. O.H. 3685' - 3714'. Squeezed 5 1/2"  
w/275 sx. cement blend w/500# hulls mixed in to Max. P.S.I. 500#.  
Close in P.S.I. 400#. Squeezed 8 5/8" w/75 sx. cement blend to Max.  
P.S.I. 150#. Close in P.S.I. 150#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 30 1992

Remarks:

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

I did [X] / did not     observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

INVOICED  
DATE 11-16-92  
AMOUNT 367.49