

6 040333

15-065-03295-0000

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE-NW-SW, SEC. 36, T 10 S, R 91

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Schneider Well # A-7

Operator: Kaiser-Franco Oil Co.

County Stahorn 120.84

Name & Address: 6733 S. Yale

Well Total Depth 3718 feet

Box 21468

Conductor Pipe: Size — feet —

Tulsa, Ok.

Surface Casing: Size 8 5/8 feet 225' w/125

Abandoned Oil Well Gas Well Input Well SWD Well RECEIVED

Other well as hereinafter indicated _____ STATE CORPORATION COMMISSION

Plugging Contractor Sun Conty License Number MAR 18 1985

Address Hays, KS 67601 CONSERVATION DIVISION
Wichita, Kansas

Company to plug at: Hour: _____ Day: 6 Month: 3 Year: 19 85

Plugging proposal received from Ray Ynutser

(company name) Kaiser-Franco (phone) _____

were: 5 1/2" casy set @ 3690' w/150 sx. Perfs set @ 3549-52
to 3606-11; dakota leak @ 1113' & squeezed w/200. sx emt;
dakota leak @ 1250' set plug @ 3530'; also sq. 1460' w/300sx
Ordered: 175 sx. emt. 60% poz 10% gel, 20 sx gel, 5 sx hulls

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:30pm Day: 6 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Ran tbg to 3440', pmcd 55sx emt w/hulls;
pulled tbg to 3200', pmcd 10sx gel w/hulls; pulled to 2200'; pmcd
10sx gel w/hulls; pulled to 1150', pmcd 50sx emt w/hulls; pulled
to 500', pmcd 50 emt to circr emt. pulled tbg & filled to surf.
Hooked-ups 8 5/8" S.P. pmcd in 60-70sx emt. w/hulls
P.S. I - 450# Shurin 300#

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE 3-19-85
INV. NO. 7392

Signed Dennis J. Hamel 3-15-85
(TECHNICIAN)