

9-30

4-041933

15-065-01826-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1958

NE SE NE /4 SEC. 36, 10 S, 21 W  
990 feet from N section line  
330 feet from W section line

Operator license# 5447

Lease: Trico West Unit Well # 111

Operator: OXY USA, Inc.

County: Graham 12/13

Address: Drawer D  
Plainville, Kansas 67663

Well total depth 3727 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 240 Feet  
W/200 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 30 Month: September Year 1997

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 5 1/2" casing set at 3717' w/175 sxs cement.  
Perfs at 3553' - 3600'. Anhy. At 1625' w/600 sxs cement.  
Ordered 250 sxs 60/40 pozmix - 10% gel with 1/4# F.C. - 400# hulls.

11-5-97

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 12:00 P.M., Day: 30, Month: September, Year: 1997

Actual plugging report: R.I.H. with tubing to 3500' - spotted 12 sxs gel, followed with 100 sxs cement with 200# hulls. Pulled to 1600' - spotted 110 sxs cement to circulate at surface. P.O.O.H. Squeezed casing to 500# with 20 sxs cement. 8 5/8" - pressured up to 300#. Job complete.

Remarks:  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO  
Elevation: G.L.

I did[ X ] / did not[ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

DATE NOV 06 1997

INV. NO. 49448

9-30 JAN 09 1998