

4-060598

10-25 15-065-01815-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 12-28-55

SW NE SE /4 SEC. 36, 10 S, 21 W  
1650 feet from S section line  
990 feet from E section line

(Formerly Fondoble #7)

Operator license# 5447

Lease Trico Unit West well # 107

Operator: OXY-USA, Inc.

County Graham

Address: 110 S. Main  
Suite #800  
Wichita, Kansas 67202

Well total depth 3705 feet <sup>120.41</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 240 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Company License#           

Address: Wichita, Kansas 67202

Company to plug at: Hour: 8:30A.M. Day: 25 Month: October Year: 94

Plugging proposal received from: Don Shelton

Company: OXY-USA, Inc. Phone: 913-4343-7681

Were: Order 300 sxs. 60/40 posmix - 10% gel and hulls.  
Plug with tubing.  
Casing leak at 2968' to 2998'.  
Several squeezed at 1082' - 1113' to repair prior leaks.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:30A.M., Day: 25, Month: October, Year: 94

Actual plugging report: 8 5/8" to 240'. 5 1/2" to 3699' w/175 sxs.  
Two staged from D.V. set at 1608' to surface with 400 sxs. cement and  
200 cu. ft. of stratacrete. Ran tubing to 3531' and pumped 75 sxs.  
cement with 200# hulls. Pulled tubing to 2309' and pumped 75 sxs. cement  
with 200# hulls. Pulled tubing to 1087' and circulated cement with  
60 sxs. Pulled tubing. Tied onto production casing and pumped 75 sxs.  
cement. Max. P.S.I. 500#. S.I.P. 500#. Annulus full of cement.

Remarks: Halliburton Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 2135

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1994

CONSERVATION DIVISION  
WICHITA, KANSAS

I did  did not  observe the plugging.

*[Signature]*

AT (agent)

DATE 11-2-94

INV. NO. 41564