

4-031853

9-2 15-065-01818-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1954

NW SE SW /4 SEC. 36, 10 S, 21 W
990 feet from S section line
3630 feet from E section line

Operator license# 6568

Lease Schneider well # A 3

Operator: Kaiser-Francis Oil Company

County Graham

Address: P.O. Box 21468
Tulsa, OK 74121-1468

Well total depth 3699 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 210 feet

120.21

Aband. oil well X, Gas well __, Input well __, SWD __, D & A __

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 2 Month: September Year: 93

Plugging proposal received from: Gordon

Company: Kaiser-Francis Oil Company Phone: _____

Were: Order 350 sxs. 65/35 pozmix - 10% gel. - 500# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:50 P.M., Day: 2, Month: September, Year: 93

Actual plugging report: 8 5/8" set @ 210' w/125 sxs. 5 1/2" set @ 3685' w/150 sxs. O.H. 3685' - 3699'. Squeezed @ 1263' and 867' w/400 sxs. Shots @ 1600' and 2120'. Ran tubing to 2500'. Circulated cement to surface. Squeezed 5 1/2" w/350 sxs. cement blend w/300# hulls to Max. P.S.I. 500#. Close in P.S.I. 150#. Squeezed 8 5/8" w/50 sxs. cement blend to Max. P.S.I. 150#. Close in 150#. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD X BAD ____ Anyh. plug: YES X NO ____
Bottom plug(in place): YES __, CALC X, NO ____ Dakota plug: YES X, NO ____
Plugged through TUBING X, CASING __. Elevation: ____ GL

I did [X] / did not [] observe the plugging.

Carl Goodrow

(agent)

RECEIVED STATE CORPORATION COMMISSION

SEP 22 1993

DATE

9-28-93

INV. NO.

38803

Form CP-2/ CONSERVATION DIVISION
Wichita, Kansas