

11-26 15-005-20757-000114  
R

4- 031614

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- -  
NW SW NW /4 SEC. 14, 10 S, 22 W  
3630 feet from S section line  
4950 feet from E section line

Operator license# 4767 Lease Holmquist Holmes well # 1

Operator: Ritchie Exploration Inc. County Graham

Address: 125 N. Market #1000 Well total depth 3935 feet <sup>127.88</sup>  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 272 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cement Company License#    

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 26 Month: November Year: 91

Plugging proposal received from: John Niernberger

Company: Ritchie Exploration Inc. Phone:    

Were: Order 450 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Allied Cement Company. Run tubing to guarantee cement  
placement. Using Ritchie's packers to test casing. Holes were  
found from 669' to 3024' - which indicated that additional  
shot holes were not necessary.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 6:00P.M., Day: 26, Month: November, Year: 91

Actual plugging report: 8 5/8" @ 272' w/160 sks. 4 1/2" @ 3778' w/150  
sks. Top perf. @ 3496'. Pump in 2 3/8" tubing w/100 sx. cement @ 3171'.  
50 sx. and 200# hulls @ 2717'. 75 sx. and 350# hulls @ 1280'. Cement  
circulated to surface. Layed down tubing. Loaded 4 1/2" w/50 sx.  
cement blend w/200# hulls mixed in. Squeezed 8 5/8 w/25 sx. cement blend  
to max. P.S.I. 500#. Close in P.S.I. 500#. Tied onto 4 1/2" squeeze to  
positive pressure with 25 sx. cement blend. Used total of 300 sx.  
cement blend. Pressure broke down. Slight vac. T.A.G. 11-27-91 @ 241'.  
Fill w/25 sx. 50/50 pozmix. Max. pressure on 4 1/2" - 300 P.S.I.  
Remarks: Shut in @ slight vac P.S.I. broke down. Max. pressure on  
backside - 500 P.S.I. Shut in @ 500 P.S.I. Total sacks 325 cement.

**INVOICED**

RECEIVED  
STATE CORPORATION COMMISSION

Carl Goodrow

DATE 1-7-92  
INV. NO. 34228

DEC 16 1991

M.S.

(agent)

Form CP-2/3