

9-29

4-031862

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-005-20897-0000

NW NW NW /4 SEC. 14, 10 S, 22 W
4950 feet from S section line
4950 feet from E section line

Operator license# 4767

Lease Holmquist Holmes well # 3

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market
Suite #1000
Wichita, Kansas 67202

Well total depth 3760 feet ^{122.20}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 131 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Paul's Well Service License#

Address: 411 Jefferson, Ellis, Kansas 67637

Company to plug at: Hour: P.M. Day: 29 Month: September Year: 93

Plugging proposal received from: John Niernberger

Company: Ritchie Exploration, Inc. Phone:

Were: Order 275 sxs. 60/40 pozmix - 10% gel. - 500# hulls.
Allied Cement Company.
Emergency plug permitted - rig over hole.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:30P.M., Day: 29, Month: September, Year: 93

Actual plugging report: 8 5/8" set @ 131' w/150 sxs. cwc. 4 1/2" set @
3752' w/150 sxs. Squeezed 1034' w/200 sxs. 1374' w/200 sxs. Holes in
4 1/2" casing. Ran tubing to 2620' - mix and pump 50 sxs. cement blend
w/200# hulls. Lay down tubing to 1500' - mix and pump cement blend to
circulate cement slurry. Lay down tubing. Squeeze 4 1/2" casing with
total of 200 sxs. cement blend with 500# hulls mixed in to Max P.S.I.
300#. Close in P.S.I. 100#. Squeeze 8 5/8" with 75 sxs. cement blend to
Max. P.S.I. 300#. Close in P.S.I. 100#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD X Anyh. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
Wichita, Kansas

(agent)
Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1993
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE OCT 19 1993
INV. NO. 38969