

4-031825

6-7

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-21,037-0000

SE NE NW /4 SEC. 14, 10 S, 22 W
4290 feet from S section line
2970 feet from E section line

Operator license# 4767

Lease Holmquist-Holmes well # 5

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market
Suite 1000
Wichita, Kansas 67202

Well total depth 3797 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 204 feet

123.40

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Express Well Service License#

Address: Victoria, Kansas 67671

Company to plug at: Hour: P.M. Day: 7 Month: June Year: 93

Plugging proposal received from: Peter and Dennis Hamel District #4

Company: Ritchie Exploration, Inc. Phone:

Were: Order 225 sxs. 60/40 pozmix - 10% gel.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:00P.M., Day: 7, Month: June, Year: 93

Actual plugging report: 8 5/8" set @ 204' w/170 sx. cwc. 4 1/2" set @
3785' w/125 sx. Squeezed @ 1010' - 1025' w/200 sx. CIBP @ 3520'.
Perf. 3710' - 3679'. Shot @ 2500' (below salt). Ran tubing to 2500'.
Spot cement to surface. Squeezed 4 1/2" with total of 215 sx. with
cement at surface. Squeeze 8 5/8" with 60 sx. to max. P.S.I. 450#.
Close in P.S.I. 150#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: GL

I did not observe the plugging.

Carl Goodrow

DA (agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1993
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
DATE JUL 13 1993
38102