

4-041817

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-22

API Number: 15-065-21,176-0000
200' W.
SW NE NW /4 SEC. 22, 10 S, 22 W
4290 feet from S section line
3830 feet from E section line

Operator license# 5399

Lease: Weigel Well # 1

Operator: American Energies Corporation

County: Graham 130.00

Address: 115 N. Market - Suite #710
Wichita, Kansas 67202

Well total depth 4000 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 200 feet
w/165sx.cmt.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 22 Month: October Year 1996

Plugging proposal received from: Alan Degood

Company: American Energies Corporation Phone:

Were: Order 300 sxs 60/40 pozmix with 10% gel with 1/4# F.C. - 500# hulls.
4 1/2" casing set at 4000' w/250 sxs cement. Perfs at 3620' - 3760'. Salt at 2150' Anhy
at 1839' - Dakota at 1050'.

11-6-96

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

11-06-96
11:35
11-06-96

Completed: Hour: 11:30 P.M., Day: 22, Month: October, Year: 1996

Actual plugging report: R.I.H. with perforators to perf at 2150' - 1839' - 1050'. Squeezed
8 5/8" casing with 40 sxs cement and 100# hulls. Max. P.S.I. 300#. Squeezed down 4 1/2"
casing with 260 sxs cement with 400# hulls. Max. P.S.I. 400#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING . Elevation: GL

and X / did not [] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED

DATE 11-7-96

INV. NO. 46929