

15-065-20440-0000

6 041224

API NUMBER 15- 1981

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NE, SEC. 22, T 10 S, R 22 W/E
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6622

Lease Name J. Faulkner Well # 1

Operator: Jason Oil Inc.

County Graham 124.02

Name & Address: Box 701

Well Total Depth 3816 feet

Russell, Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 252 w/175 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Kansas

Company to plug at: Hour: 10:00AM Day: 20 Month: Sept Year: 19 90

Plugging proposal received from Jim Schoenberger

(company name) Jason Oil (phone) _____

were: 4 1/2 casing set at 3814 w/250 sks cement: perfs at 3564. Perf base dakota at

1025. Sq at 1800 to 2000 w/400 sks: Sq 2732 -3205 w/200 sks. Ordered 350 sks 65/35 poz

10% gel w/1/2 lb f.c. plus 5 sks hulls. Ran w.l.m. 1700. Anhydrite at 1808.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 PM Day: 20 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 4 1/2 casing w/25 sks cement w/1/2 lb. f.c.

plug pumped in add 275 sks cement w/1/2 lb. f.c. and 5 sks hulls mixed in cement. Max 500 lbs.

S.I. 300 lbs. pumped in 8 5/8 casing w/50 sks cement w/1/2 lb f.c. mixed in cement. Max 300 lbs.

S.I. 100 lbs. Hole in casing at 1325.

RECEIVED STATE CORPORATION COMMISSION

OCT 3 1990

Remarks: _____ (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE OCT 05 1990

INV. NO. 29542 9-20

MAR 07 1991

Signed Dennis Hamel (TECHNICIAN)
Dennis Hamel