

9-30

4-032264

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-21,935-0000

SW NW _____ /4 SEC. 22, 10, 22 W
3300 _____ feet from S section line
4620 _____ feet from E section line

Operator license# 5399

Lease: Weigel Well # 4

Operator: American Energies Corporation

County: Graham 125.06

Address: 155 North Market - #710
Wichita, Kansas 67202

Well total depth 3848 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 262 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 30 Month: September Year: 1997

Plugging proposal received from: Butch (Lawrence Jackson)

Company: American Energies Corporation Phone: -

Were: Order 190 sxs 60/40 pozmix - 10% gel - 300# hulls.
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow 10-14-97

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 1:15 P.M., Day: 30 Month: September Year: 1997

Actual plugging report: 8 5/8" set at 262' w/175 sxs. 4 1/2" set at 3848' w/150 sxs.
Prod. Perfs 3770' - 3776'. Sand back to 3720' with 4 sxs common cement on sand with bailer.
Recovered 520' of 4 1/2" with shots at 1800' - 1200'. Mixed and pumped down 4 1/2" 80 sxs
cement blend with 300# hulls to circulate. Plug complete.

Remarks:

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES , NO _____

Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

①

DATE 10-22-97

INV. NO. 49215

9-30