

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01845-00-01  
Spot: CN2NWSE Sec/Twnshp/Rge: 6-10S-23W  
2310 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: HOFF NW Well Number: 401W  
County: GRAHAM Total Vertical Depth: 3995 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 217 150 SX CMT  
Production: Size 5.5 feet: 3995 100 SX CMT  
Liner: Size feet: 129.84

Well Type: EOR UIC Docket No: E16528.4 Date/Time to Plug: 09/10/2001 10:45 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GRESTER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Well squeezed with 275 sxs at 1522' in 1966.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/10/2001 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:


Tied onto 5 1/2" and pumped to pressure with 300 sxs and 500# hulls.  
Max. P.S.I. 600#. S.I.P. 500#.  
Hooked onto 8 5/8" annulus with instant pressure 300#.

Remarks: LEASE ALSO KNOWN AS JOHNSON B-#1. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

RECEIVED

SEP 14 2001

KCC WICHITA

INVOICED

DATE

9-14-01

INV. NO.

2002060466

Form CP-2/3

SEP 12 2001

6-10-23w

IMPERIAL OIL OF KANSAS #1 JOHNSON 'B' N2: NW-SE


Contr. IMPERIAL OIL GRAHAM County

E 2 1/4 10RB Comm. Comp. 2-7-58 IP 199 BOPD

Tops	Depth	Datum
ANH	2047	393
HEEB	3744	-1304
TOR	3768	-1328
LANS	3783	-1343
TD	3995	-1555

Casing  
8" 217  
5" 3995

DST 3820-48/2 HR, 70' WTR,  
BHP 1070#  
DST 3928-44/2 HR, G/80",  
860' OIL, BHP 950#  
PERF 32/3939-43: 3 BOPH, NATL  
HOOF NW POOL ACID 500: SWB  
11 1/2 BOPH/3 HR  
ACID 5000: SWB  
15 1/2 BOPH/4 HR



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS