

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00603-00-01  
Spot: SWSENE Sec/Twnshp/Rge: 6-10S-23W  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: HOFF NW Well Number: 301W  
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 195 150 SX CMT  
Production: Size 5.5 feet: 4038 200 SX CMT  
Liner: Size feet:

\$131.30

Well Type: EOR UIC Docket No: E16528.6 Date/Time to Plug: 09/10/2001 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GRESTER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/10/2001 10:45 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 5 1/2" and pumped to pressure with 300 sxs and 500# hulls.  
Max. P.S.I. 600#. S.I.P. 400#.  
Hooked onto 8 5/8" annulus and pumped 75 sxs.  
Max. P.S.I. 300#. S.I.P. 100#.

Remarks: LEASE ALSO KNOWN AS JOHNSON C-#1. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

RECEIVED  
SEP 14 2001  
KCC WICHITA

INVOICED  
DATE 9-14-01  
WV NO. 2002060466

SEP 12 2001

FRANCIS OIL & GAS & H G #1 JOHNSON 'C' SW SE NE  
 KAISER  
 Contr. ARMER DRLG CO GRAHAM County  
 E 2422RB Comm. Comp. 5-16-58 IP 132 BOPD  
 PHY POT

Tops	Depth	Datum
ANH	2021	401
HEEB	3731	-1309
LANS	3757	-1335
TD	4044	-1622

Casing  
 8" 192  
 5" 4038  
 DST 3726-81/70", 40' o SPK M, BHP 660#  
 DST 3779-3823/1 HR, 20' V SL OCM, BHP 850#  
 DST 3875-3922/2 HR, 3540' GIP, 45' GCM,  
 60' HO & GCM, 540' FROG o, 300' FR o,  
 BHP 1040#  
 DST 3918-72/2 HR, 660' GIP, 40' GCM, 60' o  
 & GCM, 20' FROG o, 360' GSY o, 120' oc  
 MDY w, 180' w, BHP 1090#  
 DST (STRAD) 3812-45/2 HR, 170' GSY M, 120'  
 ocm, 180' o & GCM, 60' VH OCM, BHP 1205#  
 DST 3691-3726/1 HR, 2540' SW, BHP 1255#  
 HOOFF NW POOL SWB 3 BOPH @ 3910-16:  
 ACID 3500: SWB 30 BOPH

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS