

15-065-03297-0002
5-25

4-031934

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

NE SW NW /4 SEC. 02 , 10 S, 23 W
3630 feet from S section line
4290 feet from E section line

Operator license# 5363

Lease Griffith well # 5

Operator: Berexco, Inc.

County Graham

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 4147 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 278 feet

134.77

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Company Tools License# 3079 Rig Tag

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 25 Month: May Year: 9

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order sxs. 60/40 pozmix - 10% gel - 500# hulls.
Emergency plug. Rig over the hole with bad casing. Decision to plug.
Wahed down to 2730'. Wireline found fluid at 430' - TD 1065'.
Washed down to 2730' - hit possible casing. Collapse couldn't go any
deeper - fluid dropped.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:20P.M., Day: 25, Month: May, Year: 94

Actual plugging report: 8 5/8" set @ 278' w/175 sxs. 5 1/2" set @
4147' w/200 sxs. PBSD 4130'. Prod. perf 3709' - 4121'. Perf. critical
area control shots at 2020' and 1200' - ran tubing to 2700' circulated
cement blend slurry to surface 100 sxs. - 250# hulls at 2700'. Pulled
to 1360' w/125 sxs. to circulate with 250# hulls. Max. 300# P.S.I.
Close in P.S.I. 200#. Squeezed 8 5/8" w/25 sxs. cement blend slurry
to Max. P.S.I. 300#. Close in P.S.I. 200#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

RECEIVED
JUN 03 1994

I did X did not observe the plugging.

Carl Goodrow
CONSERVATION DIVISION
Wichita, Kansas

(agent)
Form CP-2/3

INVOICED
DATE 6-6-94
INV. NO. 40534
525

AUG 11 1994