

4-032126

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

12-29

API Number: 15- - 1953

S2 NW NW /4 SEC. 02, 10, 23 W  
4290 feet from S section line  
4620 feet from E section line

Operator license# 5363

Lease: Griffith Well # 4

Operator: Berexco, Inc.

County: Graham

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 4170 <sup>135.53</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 262 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 29 Month: December Year: 1995

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 350 sxs 60/40 pozmix - 10% gel - 15 sxs gel - 650# hulls.  
Order work string.

RECEIVED  
STATE CORPORATION COMMISSION

Plugging Proposal Received by: Carl Goodrow

JAN 16 1996

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 6:26 P.M., Day: 29, Month: December, Year: 1995

Actual plugging report: 8 5/8" set at 262' cwc with 150 sxs. 5 1/2" set at 4220' with 200sxs. Prod. Perf. 3791' - 3900'. Squeezed 1189' - 1220' w/48 sxs. Squeezed 2009' - 3775' with 555 sxs. Ran tubing to 3695' - displaced 15 sxs gel - 100 sxs cement with 500# hulls. Pulled tubing to 2000' - displaced 75 sxs cement with 150# hulls. Pulled tubing to 976' circulated cement to surface. Squeezed 5 1/2" with total of 270 sxs cement to Max. P.S.I. 800#. Squeezed 8 5/8" with 50 sxs cement to Max. P.S.I. 100#. Plug complete.

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING. KGC Elevation: GL

If did not observe the plugging JAN. 11 1996 Carl Goodrow (agent)

INVOICED  
DATE JAN 17 1996  
INV. NO. 44634

HAYS, KS Form CP-2/3

Handwritten signature/initials