

4-032127

15-065-03307-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

1-9

API Number: 15- - 1951

NE NW NW /4 SEC. 02, 10, 23 W
4950 feet from S section line
4290 feet from E section line

Operator license# 5363

Lease: Griffith Well # 1

Operator: Berexco, Inc.

County: Graham

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 4143 ^{134.65} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 245 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 9 Month: January Year: 1996

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 500 sxs 60/40 pozmix - 10% gel - 1000# hulls.

RECEIVED
STATE CORPORATION COMMISSION
1-23-96
JAN 23 1996

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 8:00 P.M. Day: 9 Month: January Year: 1996

Actual plugging report: 8 5/8" set at 245' cwc with 150 sxs. 5 1/2" set at 4142' with 300sxs. Prod. Perf. 3768' - 3919'. Squeezed 1611' w/125 sxs. - 1086' w/200 sxs. PBT 4098'. Sanded bridge at 3736' - clean out to 3780+. Backed off tubing at 3692'. Spotted 100 sxs cement with 500# hulls. Ran tubing to 2211' - pumped 100 sxs cement blend with 150# hulls. Pulled tubing to 762' - circulated with 55 sxs cement blend with 200# hulls. Pulled tubing. Tied onto 5 1/2" - pumped 25 sxs to Max. P.S.I. 500#. Held. Squeezed 8 5/8" with 85 sxs cement blend with 150# hulls to Max. P.S.I. 250#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING Elevation: GL

I did [X] did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 1-26-96

INV. NO. 44731