

**CONFIDENTIAL**

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

**ORIGINAL**

Form ACO-1  
September 1999  
Form must be Typed

**WELL COMPLETION FORM**

**WELL HISTORY - DESCRIPTION OF WELL & LEASE**

Operator: License # 32309  
Name: Presco Western, LLC  
Address 5665 FLATIRON PARKWAY  
City/State/Zip BOULDER CO 80301  
Purchaser: High Sierra Crude/EP  
Operator Contact Person: Randy M. Verret  
Phone ( 303 ) 305-1163  
Contractor: Name: Xtreme Coil Drilling Corporation  
License: 33976

Wellsite Geologist: Not Applicable

Designate Type of Completion

New Well  Re-Entry  Workover

Oil  SWD  SIOW  Temp. Abd.

Gas  ENHR  SIGW

Dry  Other (Core, WSW, Expl., Cathodic, etc.)

If Workover/Reentry: Old Well Info as follows:

Operator: \_\_\_\_\_

Well Name: \_\_\_\_\_

Original Comp. Date \_\_\_\_\_ Original Total Depth \_\_\_\_\_

\_\_\_\_\_ Deepening \_\_\_\_\_ Re-perf. \_\_\_\_\_ Conv. to Enhr./SWD

\_\_\_\_\_ Plug Back \_\_\_\_\_ Plug Back Total Depth \_\_\_\_\_

\_\_\_\_\_ Commingled \_\_\_\_\_ Docket No. \_\_\_\_\_

\_\_\_\_\_ Dual Completion \_\_\_\_\_ Docket No. \_\_\_\_\_

\_\_\_\_\_ Other (SWD or Enhr?) \_\_\_\_\_ Docket No. \_\_\_\_\_

10/25/2007 11/7/2007 11/7/2007

Spud Date or Date Reached TD Completion Date or Recompletion Date

API NO. 15- 081-21762-0000

County Haskell

SE - NW - NE - SW Sec. 24 Twp. 30 S. R. 34  E  W

650 Feet from S/N (circle one) Line of Section

1,930 Feet from E/W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW SW

Lease Name Stalker Well # 19-C24-30-34

Field Name Victory

Producing Formation Morrow/St. Louis

Elevation: Ground 2,961' Kelley Bushing 2,973'

Total Depth 5,628' Plug Back Total Depth \_\_\_\_\_

Amount of Surface Pipe Set and Cemented at 1,761' Feet

Multiple Stage Cementing Collar Used?  Yes  No

If yes, show depth set 3,353' Feet

If Alternate II completion, cement circulated from \_\_\_\_\_

feet depth to \_\_\_\_\_ w/ \_\_\_\_\_ sx cmt.

Drilling Fluid Management Plan ATTN: 3-31-09  
(Data must be collected from the Reserve Pit)

Chloride content 3,000 ppm Fluid volume 1,500 bbls

Dewatering method used Air Evaporation

Location of fluid disposal if hauled offsite: \_\_\_\_\_

Operator Name \_\_\_\_\_

Lease Name \_\_\_\_\_ License No. \_\_\_\_\_

Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  E  W

County \_\_\_\_\_ Docket No. \_\_\_\_\_

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature \_\_\_\_\_


Title Manager Business and Regulatory Affairs Date 11/12/2008

Subscribed and sworn to before me this 9th day of January, 2008

Notary Public Kathleen F. [Signature]

Date Commission Expires 2-12-2011

**CONFIDENTIAL**  
JAN 09 2008  
KCC



**KCC Office Use ONLY**

Letter of Confidentiality Received  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 10 2008  
CONSERVATION DIVISION  
WICHITA KS

Operator Name Presco Western, LLC

Lease Name Stalker

Well # 19-C24-30-34

Sec. 24 Twp. 30 S.R. 34  East  West

County Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets.)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datums	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Heebner	4,027'	-1,054'
Electric Log Run (Submit Copy.)	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Lansing	4,095'	-1,122'
List All E.Logs Run:		Iola	4,385'	-1,412'
Compensated Neutron/Density PE Log, Dual Induction Log, Sonic Log		Swope	4,576'	-1,603'
		Hertha	4,632'	-1,659'

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8	23.0	1,763'	ALW	575	6%gel/3%CC
					Class C	150	3%CC
Production	7 7/8	5 1/2	15.5	4,912'	ASC	95	2%gel/10%salt

ADDITIONAL CEMENTING/SQUEEZE RECORD				
Purpose	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input checked="" type="checkbox"/> Protect Casing	3,353'	Lite	450	60/40 8% Gel, 1/4 Flo Seal
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4,762' - 4,768' (Marmaton)	6 bbls Acid/28 bbls flush	

TUBING RECORD	Size 2 7/8	Set At 4,663'	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr.	Producing Method			
1/03/2008	<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls. 52	Gas Mcf 109	Water Bbls. 18	Gas-Oil Ratio 2,096
				Gravity 37.5

Disposition of Gas:  Vented  Sold  Used on Lease  Open Hole  Perforation  Dually Comp.  Commingled

(If vented, submit ACO-18.)  Other (Specify) \_\_\_\_\_

METHOD OF COMPLETION \_\_\_\_\_

Production Interval \_\_\_\_\_

# ALLIED CEMENTING CO., INC.

28875

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Li BEARL 45

DATE <u>12-5-07</u>	SEC. <u>24</u>	TWP. <u>30S</u>	RANGE <u>34W</u>	CALLED OUT	ON LOCATION	JOB START <u>1:00 pm</u>	JOB FINISH <u>2:30 pm</u>
LEASE <u>Stallen</u>	WELL # <u>19-</u>	LOCATION <u>Sawata W+S into</u>		COUNTY <u>Haskell</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one)							

CONTRACTOR Codell #1

TYPE OF JOB Pant Collar

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 15.5 DEPTH 5628'

TUBING SIZE 3 3/4 2 1/4 DEPTH 3320

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL Pant Collar DEPTH 3320

PRES. MAX 1500 psi MINIMUM 150 psi

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER JANE

CEMENT AMOUNT ORDERED 450 SK

60/40 8% GEL 1/4 FLO SEAL

EQUIPMENT

PUMP TRUCK CEMENTER BOB/ABLE

# 417 HELPER GABE

BULK TRUCK DRIVER DON

# 456/239

BULK TRUCK DRIVER \_\_\_\_\_

# \_\_\_\_\_

COMMON \_\_\_\_\_

POZMIX \_\_\_\_\_

GEL \_\_\_\_\_

CHLORIDE \_\_\_\_\_

ASC \_\_\_\_\_

450 LITE 60/40/8% @ 11.25 5062.50

FLO SEAL 113 @ 2.00 226.00

HANDLING 486 @ 1.90 923.40

MILEAGE .09 SK/mi 1487.16

TOTAL 7699.06

CONFIDENTIAL  
JAN 09 2008  
KCC

REMARKS:

11 Amp casing 1500 PSI

OPEN TOOL

Mix 450 SK CNT

Loose Gravel @ 10 SK LEFT

Disp TB6 19 BBL

Rein 2 joints Reverse Clean

25 BBL TBL

CHARGE TO: PRESO WESTERN

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE

DEPTH OF JOB 3320'

PUMP TRUCK CHARGE 955.00

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE 34 @ 6.00 204.00

MANIFOLD @ \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 10 2008  
PLUG & FLOAT EQUIPMENT  
CONSERVATION DIVISION  
WICHITA, KS

TOTAL \$ 1159.00

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

Joe Artonis  
PRINTED NAME

# ALLIED CEMENTING CO., INC. 25406

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Liberal

DATE <u>11/7/07</u>	SEC. <u>24</u>	TWP. <u>30s</u>	RANGE <u>34W</u>	CALLED OUT	ON LOCATION	JOB START <u>11:00AM</u>	JOB FINISH <u>12:30PM</u>
LEASE <u>Stalker</u>	WELL # <u>19-C</u>	LOCATION <u>Jet 56 + 190 1/2 S 3/4 W S1S</u>			COUNTY <u>Haskell</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Xtreme  
 TYPE OF JOB Cmt 5 1/2 Prod. CSG  
 HOLE SIZE 7 7/8 T.D. 5620  
 CASING SIZE 5 1/2 15.50 DEPTH 5620 4912  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL Port collar DEPTH 3353  
 PRES. MAX 1150 MINIMUM 100  
 MEAS. LINE SHOE JOINT 41.14  
 CEMENT LEFT IN CSG.  
 PERFS.  
 DISPLACEMENT 116 BBL

OWNER Same

**EQUIPMENT**

PUMP TRUCK CEMENTER Max  
 # 388 HELPER Abel  
 BULK TRUCK  
 # 457-463 DRIVER Cabe  
 BULK TRUCK  
 # DRIVER

CEMENT  
 AMOUNT ORDERED  
95 sks A.S.C. + 29 bags 10% salt  
5# Gilsomite 290 FL-160

COMMON	<del>95 sks</del>	@		
POZMIX		@		
GEL	<u>2.5T</u>	@	<u>16.65</u>	<u>33.30</u>
CHLORIDE		@		
ASC	<u>95 sks</u>	@	<u>14.90</u>	<u>1415.50</u>
Salt	<u>10 sks</u>	@	<u>19.20</u>	<u>192.00</u>
Gilsomite	<u>475#</u>	@	<u>.70</u>	<u>332.50</u>
FL-160	<u>45#</u>	@	<u>10.65</u>	<u>479.25</u>
		@		
		@		
WFR II	<u>500gal</u>	@	<u>1.00</u>	<u>500.00</u>
		@		
		@		
HANDLING	<u>122 sks</u>	@	<u>1.90</u>	<u>231.80</u>
MILEAGE	<u>94/95/1M.</u>			<u>329.40</u>
				<u>TOTAL 3513.75</u>

**REMARKS:**

Pump 500gal WFR II Mix 95 sks  
Cmt Washup Pump + Lines, Prod Plug  
Displace 117 BBL Land Plug  
Floater Held

**SERVICE**

DEPTH OF JOB	<u>4912</u>		
PUMP TRUCK CHARGE			<u>1750.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>30mi</u>	@	<u>6.00</u> <u>180.00</u>
MANIFOLD <u>Head Rental</u>		@	<u>100.00</u>
		@	
		@	
			<u>TOTAL 2030.00</u>

CHARGE TO: Presco Western

STREET

CITY

AP Approval Stamp - Drilling Well		
Well Name	STATE	ZIP
Company	<u>Presco Western, LLC</u>	<u>700</u>
Cost Center		Date
AFE	<u>07106 KS</u>	
Approval		
GL Code	<u>IDC 8000 / ICC 8100 / TE 8200</u>	<u>160</u>

**PLUG & FLOAT EQUIPMENT**

<u>1-5 1/2 Triplex shoe</u>	@	<u>1550.00</u>
<u>1-5 1/2 Latch Down ASS.</u>	@	<u>410.00</u>
<u>7-5 1/2 Centralizers</u>	@	<u>50.00</u> <u>350.00</u>
<u>1-5 1/2 Cement Basket</u>	@	<u>165.00</u>
<u>1-5 1/2 Port Collar</u>	@	<u>1750.00</u>
		<u>TOTAL 4225.00</u>

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS  
**RECEIVED**  
 KANSAS CORPORATION COMMISSION

SIGNATURE

James [Signature]

**JAN 10 2008**

PRINTED NAME

CONSERVATION DIVISION  
 WICHITA, KS

# ALLIED CEMENTING CO., INC.

30286

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Liberal, Ks

DATE <u>10-27-07</u>	SEC. <u>24</u>	TWP. <u>30S</u>	RANGE <u>34W</u>	CALLED OUT	ON LOCATION	JOB START <u>2300</u>	JOB FINISH <u>0100</u>
LEASE <u>Stalker</u>		WELL# <u>19C</u>	LOCATION <u>Satanta, Ks, 3 1/2 west of 190</u>		COUNTY <u>Haskell</u>	STATE <u>Ks</u>	
OLD OR NEW <input checked="" type="radio"/> (Circle one)			<u>S. into location</u>				

CONTRACTOR Xtreme  
 TYPE OF JOB 8 3/8 Surface  
 HOLE SIZE 12 1/4 T.D.  
 CASING SIZE 8 3/8 DEPTH 1763  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX MINIMUM  
 MEAS. LINE SHOE JOINT 20'  
 CEMENT LEFT IN CSG. 20'  
 PERFS.  
 DISPLACEMENT 111 bbl

**EQUIPMENT**

PUMP TRUCK CEMENTER Jason  
 # 423-231 HELPER Max  
 BULK TRUCK  
 # 462 DRIVER Don, Terry  
 BULK TRUCK  
 # 386 DRIVER Darren

**REMARKS:**

On loc, rig up equip, mix 575 sks  
 65/35 pz @ 12.4 ppq, mix tail cmt  
 150 sks class C 370 cc @ 14.3 ppq  
 shut down, drop top plug, wash pump  
 & lines, pump displacement

CHARGE TO: Presco-Western  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

OWNER Presco Western

CEMENT  
 AMOUNT ORDERED 575 ALW 60% sel, 390cc, 1/4"  
150 sks class C 370 cc

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	<u>25 sks</u>	@ <u>46.60</u>	<u>1165.00</u>
ASC	@		
ALW	<u>575 sks</u>	@ <u>11.95</u>	<u>6813.75</u>
class C	<u>150 sks</u>	@ <u>15.40</u>	<u>2310.00</u>
Flo Seal	<u>150 lbs</u>	@ <u>2.00</u>	<u>300.00</u>
	@		
	@		
	@		
	@		
HANDLING	<u>780</u>	@ <u>1.90</u>	<u>1493.40</u>
MILEAGE	<u>30 x 786 x .09</u>		<u>2122.20</u>
			TOTAL <u>14,204.35</u>

**SERVICE**

DEPTH OF JOB	<u>1763'</u>		
PUMP TRUCK CHARGE			<u>1610.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>30</u>	@ <u>6.00</u>	<u>180.00</u>
MANIFOLD	<u>1</u>	@ <u>100.00</u>	<u>100.00</u>
		@	
		@	
			TOTAL <u>1890.00</u>

**PLUG & FLOAT EQUIPMENT**

Threadlock	<u>1</u>	@ <u>30.00</u>	<u>30.00</u>
Plugs		@ <u>100.00</u>	<u>100.00</u>
(Insect float collar)		@	
Swee Seal	<u>1</u>	@ <u>580.00</u>	<u>580.00</u>
Centralizer	<u>10</u>	@ <u>55.00</u>	<u>550.00</u>
Basket	<u>1</u>	@ <u>220.00</u>	<u>220.00</u>
			TOTAL <u>1430.00</u>

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment  
 and furnish cementer and helper to assist owner or  
 contractor to do work as is listed. The above work was  
 done to satisfaction and supervision of owner agent or  
 contractor. I have read & understand the "TERMS &  
 CONDITIONS" listed on the reverse side.

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 TAX

JAN 10 2008

CONSERVATION DIVISION  
 WICHITA, KS

TOTAL CHARGE 14,204.35  
 DISCOUNT 157.43 IF PAID IN 30 DAYS

SIGNATURE [Signature]

Allen Ellison  
 PRINTED NAME