



KANSAS CORPORATION COMMISSION 1034687
OIL & GAS CONSERVATION DIVISION

Form CP-1
March 2009

This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

OPERATOR: License #: 5056
Name: Holl, F.G., Company L.L.C.
Address 1: 9431 E CENTRAL STE 100
Address 2: _____
City: WICHITA State: KS Zip: 67206 + 2563
Contact Person: Loveness Mpanje
Phone: (316) 684-8481

API No. ~~15~~ - 15-047-21230-00-00
If pre 1967, supply original completion date: _____
Spot Description: _____
- - NW,SE Sec. 5 Twp. 24 S. R. 17 East West
1,980 Feet from North / South Line of Section
1,980 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Edwards
Lease Name: JOHNSON Well #: 3-5

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8.6250 Set at: 251 Cemented with: 235 Sacks
Production Casing Size: 4.50 Set at: 4455 Cemented with: 225 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Attached

Elevation: 2111 (G.L. / K.B.) T.D.: 4475 PBTD: _____ Anhydrite Depth: 1170
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Hulls, heavy mud, cement & plug according to KCC specifications

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Rob Long
Address: P.O. Box 308 City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 793-0915
Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 US HWY 56 Address 2: _____
City: ELLINWOOD State: KS Zip: 67526 + _____
Phone: (620) 727-3410

Proposed Date of Plugging (if known): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Submitted Electronically

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 22 2010

CONSERVATION DIVISION
WICHITA, KS

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Form	CP1 - Well Plugging Application
Operator	Holl, F.G., Company L.L.C.
Well Name	JOHNSON 3-5
Doc ID	1034687

Perforations And Bridge Plug Sets

	Perforation Base	Formation	Bridge Plug Depth
4331	4371	Cherokee Sand & Mississippi	

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- JOHNSON #3-5
Located: C NW SE, Section 5-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR; Sterling Drilling Company

COMMENCED: November 29, 1984
COMPLETED: December 5, 1984

TOTAL DEPTH: 4474'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 80 Surface Soil and Sand	Ran 8 joints new 8 5/8", 23# casing. 339.34' pipe set at 251' K.B.
80 - 250 Red Bed, Clay, Shale	Cemented with 235 sacks 60/40 Pozmix plug 3% cc. Plug down at 6:00 PM, 11-29-84, by Howco.
250 - 354 Shale	
354 - 1170 Shale, Sand, Red Bed	
1170 - 1190 Anhydrite	
1190 - 1903 Shale, Lime Stringers	
1903 - 4373 Lime and Shale	
4373 - 4383 Kinderhook Shale	
4383 - 4474 Lime and Shale	Ran 109 joints 4 1/2", 10.5# casing. 11 joints were used. 4445.58' pipe set at 4455' K.B. Cemented with 100 sacks Lite, 125 sacks 50/50 Pozmix, plus our regular flush ahead and additives. Plugged rathole and water well. Plug down at 10:40 PM, 12-5-84, by Howco.

Deviation Surveys: 3/4° at 2154'
1° at 4338'



Mark Parkinson, Governor
Thomas E. Wright, Chairman
Michael C. Moffet, Commissioner
Joseph F. Harkins, Commissioner

January 22, 2010

Loveness Mpanje
Holl, F.G., Company L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

Re: Plugging Application
API 15-047-21230-00-00
JOHNSON 3-5
SE/4 Sec.05-24S-17W
Edwards County, Kansas

Dear Loveness Mpanje:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after July 21, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,
Production Department Supervisor

cc: District 1

(620) 225-8888