

State of Kansas



FORM - CP-2
Rev. 9-8-64

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1967
12-05-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-195-20051-00-00

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Co., has this
date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 Wichita Plaza, Wichita, Kansas.

Lease Name: Rohn Well No. 1

Location: SE-SE-NW Sec. 10 Twp. 12 Rge. (E)(W) 22

County Trego Total Depth 4115 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

211'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Dakota section from 800' to 975'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

N. L. Nichols
Conservation Division Agent