



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-195-20239-00-00

RECEIVED
STATE CORPORATION COMMISSION
01-10-1973
JAN 10 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Black Petroleum, Incorporated,

Complete Address: 445 O. W. Garvey Building, Wichita, Kansas.

Lease Name: Babb Well No. 1

Location: App.-CW/2-NW-NE Sec. 9 Twp. 12 Rge. (E)(W) 22

County: Trego Total Depth 4108' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 675'. (LANDOWNER WISHES WELL TO BE LEFT OPEN FOR FRESH WATER WELL).

Circulate hole with heavy mud. Pull DP to 900' and displace 120 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP to 185' and circulate hole with clear water.

Very truly yours,

Conservation Division Agent