

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clarke of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Clarke guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: PO Box #922, Great Bend, Kansas.

Lease Name: Dietz Well No. 1

Location: 260' FNL & 2310' FWL of Sec. 17 Twp. 10 Rge. (E)(W) 23

County: Graham Total Depth 3940 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clarke was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.
3939'--4 1/2" Production casing cemented on bottom with 250 Sx. Packer set @ 3904' & top perforations from 3866' to 3872'.

Sand well back to 3725' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx. cement staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent