

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling Co, has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Pan-American Petroleum Corporation,

Complete Address: Box #432, Liberal, Kansas.

Lease Name: R. L. Zeigler Well No. 1

Location: NW-NW-SW Sec. 26 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3719' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated with 125 Sx.  
3708'--6" OD Production casing cemented on bottom with 300 Sx. Top perforations from 3698' to 3706'. Casing leak @ 1116' has been squeezed with 110 Sx. cement.

Sand well back to 3675' and set 5 Sx. cement with dump bailer. Pull 6" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent