

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. G. A. Hall of Sierra Petroleum Co. Inc. has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Company, Incorporated.

Complete Address: 211 North Broadway, Wichita, Kansas.

Lease Name: Holzhauser Well No. 1

Location: SW-SW-NW Sec. 26 Twp. 10 Rge. (E)(W) 21

County Graham Total Depth 3707 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

190'--8 5/8" Surface pipe, cement circulated with 140 Sx.
3705'--5 1/2" Production pipe cemented with 100 Sx. Well
squeezed from 1169' with 240 Sx. cement with 2300# pressure.
No top of cement on squeeze job indicated. Rods and tubing
were left in well. In attempting to salvage recovered 72 rods
approximately 1475', and 35 joints tubing approximately 1000'.

Squeeze annulus with 10 Sx. gel and 5 Sx. cement. Squeeze 5 1/2"
with 40 Sx. gel, 3 Sx. hulls and follow with 80 Sx. cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent