

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 9 - 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Roy Cook of Imperial Oil Company, has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Biden Well No. 1

Location: CE/2-NE-SE Sec. 1 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 3936' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 675'.

Circulate hole with heavy mud. Pull DP to 900' and displace 100 Sx.  
cement thru DP. Pull DP to 180' and displace 20 Sx. cement thru DP.  
Pull Dp. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent