

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-3-1966
FEB 3 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Shallow Water Ref. Co.

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: The Shallow Water Refining Company,

Complete Address: 1325 Wichita Plaza, Wichita, Kansas.

Lease Name: Holmes Well No. 1

Location: CS $\frac{1}{2}$ -SE-NW Sec. 2 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3813 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

247'--8 5/8" Surface casing, cement circulated.
3813'--4 1/2" Production casing cemented with 100 Sx. DV tool
set @ 1816' and Chem-Pack to Braden-head. Top perforations
@ 3626'.
Push plug to 3600', set rock bridge and 5 Sx. cement with
dump bailer. Pull 4 1/2" to 600' and circulate heavy gel mud.
pull 4 1/2" to 540' and displace 20 Sx. cement thru 4 1/2". Pull
4 1/2" to 240' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2"
set Rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. D. Schell
Conservation Division Agent