

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3-13-1968  
MAR 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co., has this  
date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell Kansas.

Lease Name: Brown Estate Well No. B-1

Location: NE-NE-NW Sec. 2 Twp. 10 Rge. (E)(W) 22

County Graham Total Depth 3812 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lynch was instructed to plug the well as follows:

226'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
3809'--5 1/2" casing cemented with 150 Sx.

Push plug to 3500', sand to 3450' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" casing and squeeze well using 35 sacks gel plus 5 sacks hulls  
and 130 Sx. cement staged.

Very truly yours,

Conservation Division Agent