

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
4-3-1967
APR 3 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Shallow Water Refining Company,

Complete Address: 1325 Wichita Plaza, Wichita, Kansas.

Lease Name: Brassfield Well No. 4

Location: CN/2-SW-NE Sec. 2 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3790 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

225'--8 5/8" Surface pipe, cement circulated with 200 Sx.
3786'--4 1/2" Production casing cemented with 150 Sx. Well
plugged back to 3745. Top perforations @ 3692'. Well has
been squeezed @ 1069' with 250 Sx. cement.
Sand well back to 3680' and set 3 Sx. cement with dump bailer.
Pull 4 1/2" casing to 600' and circulate heavy gel mud, pull 4 1/2"
to 540' and displace 20 Sx. cement. Pull 4 1/2" casing to 240' and
displace 20 Sx. cement. Pull 4 1/2" casing set rock bridge @ 30'
and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent