

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3-13-1968
MAR 13 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name: Brassfield Well No. 2

Location: SE-NE-NE ^{NW} Sec. 2 Twp. 10 Rge. (E)(W) 22

County Graham Total Depth 3810 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

248'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3801'--4 1/2" Production casing cemented with 100 Sx.

Push plug to 3500', sand well back to 3450' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well using 35 sacks gel plus 5 sacks gel and 130 Sx. cement staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent