

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Harold Chambers of Okmar Oil Company, has this
date requested permission to plug the following described well:

Mr. Chambers guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB & T Building, Wichita, Kansas.

Lease Name: Martin Webster Well No. 2

Location: CS/2-SW-NE Sec. 9 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3867 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Chambers was instructed to plug the well as follows:

107'--8 5/8" Surface casing, cement circulated with 60 Sx.
3863'--5 1/2" Production casing cemented on bottom with 150 Sx. 5 1/2" has
been squeezed @ 1400' with 250 Sx. cement.

Sand well back to 3850' and squeeze well with 3 sacks hulls, 6 sacks gel
and 130 Sx. cement, staged after pulling available 5 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION
16-6-1970
JUL 6 1970
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent