

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Harold Chambers of Okmar Oil Company has this date requested permission to plug the following described well:

Mr. Chambers guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Martin Webster Well No. 1

Location: NE -NE-NE Sec. 9 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3845' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Chambers was instructed to plug the well as follows:

91'--8 5/8" Surface casing, cement wirculated with 75 Sx.
3836'--5 1/2" Production casing cemented on bottom with 125 Sx. 5 1/2" has been squeezed @ 1400' with 250 Sx. cement.

Sand well back to 3825' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze well with 3 sacks hulls, 6 sacks gel and 150 Sx. cement staged.

RECEIVED
STATE CORPORATION COMMISSION
7-6-1970
JUL 6 1970
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

W. L. Nichols
Conservation Division Agent