

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Izadore Dreher of John O. Farmer, Incorporated, has this date requested permission to plug the following described well:Mr. Dreher guarantees payment of the plugging fee.Operator's full Name: John O. Farmer, IncorporatedComplete Address: 370 West Wichita Avenue, Russell, Kansas.Lease Name: Miller Well No. 1Location: NW-NW-NW Sec. 11 Twp. 10 Rge. (E)(W)21County: Graham Total Depth 3845' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Dreher was instructed to plug the well as follows:

150'--8 5/8" Surface casing, cement circulated with 125 Sx.
3843'--5 1/2" Production casing cemented on bottom. Top of perforations @
3534'. Hole in 5 1/2" casing approximately 3000'. 5 1/2" has been squeezed
in the Dakota. No attempt to recover 5 1/2".

Squeeze 5 1/2" with 1 sack hulls, 30 sacks gel and 150 Cu. Ft. cement,
staged. Squeeze annulus with 150 Cu. Ft. cement.

Very truly yours,

W. L. Dinkel
 Conservation Division Agent