

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
3-23-1973  
MAR 23 1973CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Izadore Dreher of John O. Farmer, Incorporated has this  
date requested permission to plug the following described well:Mr. Dreher guarantees payment of the plugging fee.Operator's full Name: John O. Farmer, Incorporated,Complete Address: 370 West Wichita Avenue, Russell, Kansas.Lease Name: DeYoung Well No. C-1Location: NW-NW-SE Sec. 11 Twp. 10 Rge. (E)(W) 21County: Graham Total Depth 3782' Oil Well XGas Well      Input Well      SWD Well      D & A      Lost Hole     Mr. Dreher was instructed to plug the well as follows:165'--8 5/8" Surface casing, cement circulated with 100 Sx.3777'--5 1/2" Production casing cemented on bottom with 100 Sx. Well  
plugged back to 3765'. Top of perforations from 3491' to 3495'. Well  
has been squeezed with cement in the Dakotas to surface.Squeeze 5 1/2" casing with 25 Cu. Ft. cement, 30 sacks gel and follow with  
125 Cu. Ft. cement to surface.

Very truly yours,

  
Conservation Division Agent