

15-065-03128-0000

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 11 1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address: 617 Union center, Wichita, Kansas.

Lease Name Diebolt Well No. 2

Location SE-NW-NW Sec. 14 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3885'

Abandoned Oil Well x Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company,

Address: Box # 304, Great Bend, Kansas. License No. 2

Operation Completed: Hour 5:30PM Day 8 Month 6 Year 1965

The Above well was plugged as follows:

224' -- 8 5/8" Surface pipe, cement circulated with 160 Sx.  
38385' -- 5 1/2" Production casing cemented with 100 Sx. Well plugged back  
to 3735'. Top perforations @ 3703'.

Sanded well back to 3690' and set 5 Sx. cement with dump bailer. Pulled  
5 1/2" to 600' and circulated heavy gel mud. (Used 15 Sx. gel). Pulled 5 1/2"  
to 540' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 210' and dis-  
placed 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10  
Sx. cement to bottom of cellar. (Recovered 3210' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 6/11/65

INV. NO. 1300-W