

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SE

SEC. 12TWP. 10RGE. 23

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Irwin

Operator Continental Oil Co Address Great Bend, Kans

Field _____ County Graham

Total Depth 4185 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 206' circulated with cement - 5 1/2" at 4184' with

250 sax cement behind - cement o 4109' - perforated 4064'.

Filled with chat to 4050', set 4 sax cement with dump bailer -

pulled 2918' 5 1/2" - filled with mud to 200', set rock and 20

sax cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

RECEIVED
STATE CORPORATION COMMISSION
4-26-55
APR 26 1955

CONSERVATION DIVISION
Wichita, Kansas
Eldon Bell
District Conservation Agent

DATE 4-21-55

PLUGGING
FILE SEC 12 T 10 R 23W
BOOK PAGE 114 LINE 15