

15-065-03129-0000

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
OCT 30 1967
10-30-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Skelly Oil Company,
Complete Address 1860 Lincoln Street, Denver, Colorado.
Lease Name Frank Law Well No. 1
Location NE-NE-NE Sec. 15 Twp. 10 Rge. (E) (W) 23
County Graham Total Depth 3914'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 2:00PM Day 21 Month 10 Year 1967

The above well was plugged as follows:

242'--8 5/8" Surface pipe, cement circulated with 165 Sx.
3949'--5 1/2" Production casing cemented with 200 Sx. on bottom. Well plugged back to 3914'. Top perforations from 3695' to 3697'. Staging collar set @ 3367' with oil returned to surface.

Sanded well back to 3675' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well from 3635' to 1125' with 12 sacks gel using 5 sacks hulls in initial gel. Followed with 100 Sx. cement from 1125' to 800' with 100 Sx. cement, then 12 sacks gel from 800' to 260', followed with 20 Sx. cement from 260' to 200', then 3 Sx. gel from 200' to 30' and 10 Sx. cement to bottom of cellar. Max. Pump-in pressure 400#. FSIP 250#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 10/30/67
INV. NO. 6587-W