

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 7-32

LOCATION NW NW NW

SEC. 15 TWP. 10 RGE. 23 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Law _____

Operator Imperial Oil Of Kans Address 903 Union Natl Bldg Wichita

Field _____ County Graham

Total Depth 3955 Feet.

Plugging Contractor Miller Pipe Pulling

Plugging Contractor's License No. 12

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 225' circulated with cement - 5 1/2" at 3955' with 125 sax
cement behind - perforated at 3899'

Filled with chat to 3885', set 4 sax cement with dump bailer,
pulled 2800' 5 1/2" - filled with mud to 220', set rock and 15 sax
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

[Signature]

District Conservation Agent

Date 10-23-55

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1955

CONSERVATION DIVISION
Wichita, Kansas

10-26-55

PLUGGING

FILE SEC. 15 TWP. R-23

BOOK PAGE 2 LINE 22