

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 195 - 20,519 - 00 - 00 (of this well)

Operator's Full Name Mobil C. Hoover

Complete Address NBC Plaza, Suite 302, Eldorado, Arkansas

Lease Name Duane O. Newcomer "B" Well No. 1

Location <sup>NW</sup> N/2 NE NE Sec. 6 Twp. 12 Rge. (E) (W) 22

County Trego Total Depth 3930'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 9 A Day 13 Month 12 Year 1978

The above well was plugged as follows:

RTD 3930' 8 5/8 csg set 264' cwc 160 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 950' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
12-18-1978  
DEC 18 1978

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: *H. J. Massey*  
Well Plugging Supervisor

DATE 12-19-78  
INV. NO. 8776-W