

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-195-20245-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 17 1973  
07-17-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Newcomer Well No. 1

Location APP C 512 512 SW  
440' FSL and 1320' FWL of Sec. 7 Twp. 12 Rge. (E) (W) 22

County Trego Total Depth 3680'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 7:00 PM Day 15 Month 7 Year 1973

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Cu. Ft. cement  
thru DP from 925' to 600'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru DP  
from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement from 40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 7/17/73  
INV. NO. 7641-W