

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 144-26

LOCATION NE NE SW

SEC. 16 TWP. 10 RGE. 23

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 7 Lease Stewart

Operator Skelly Oil Co Address Hutchinson, Kans

Field \_\_\_\_\_ County Graham

Total Depth 4168 Feet.

Plugging Contractor Ace Pipe Pulling

Plugging Contractor's License No. 2

Address \_\_\_\_\_  
(Describe briefly the manner in which the well was plugged)

8 5/8" at 278' circulated with cement - 5 1/2" at 4159' with

200 sax cement behind - P. B. to 3776', perforated at 3760'.

Filled with sand to 3750', set 5 sax cement with dump bailer,

pulled 5 1/2" - mudded hole to 275', set rock and 20 sax cement.

mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED  
STATE OF KANSAS

SEP 1 1955  
09-01-55

District Conservation Agent

Date 8-27-55

**PLUGGING**  
FILE SEC 16 TWP 10 R 23  
BOOK PAGE 144 LINE 26

WICHITA, KANSAS