

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21732-00-01  
Spot: SESEW , Sec/Twnshp/Rge: 4-12S-22W  
440 feet from S Section Line, 3080 feet from E Section Line  
Lease/Unit Name: ADA OWWO Well Number: 3  
County: TREGO Total Vertical Depth: 4095 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

Conductor Pipe: Size feet: \$133.09  
Surface Casing: Size 8.625 feet: 259  
Production: Size 4.5 feet: 4090  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/22/2002 10:00 AM  
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.  
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 420 cu.ft. cement slurry.

Plugging Proposal Received By: CARL GOODROW  
Date/Time Plugging Completed: 02/22/2002 11:00 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 259' w/200 sxs. 4 1/2" set at 4090' w/175 sxs.  
D.V. set at 1834' w/475 sxs cwc.  
Prod. LKC.  
Fluid level near bottom - depleted production zone.  
Filled 4 1/2" with 420 cu.ft. cement slurry.

RECEIVED

APR 19 2002  
04-19-2002  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

DATE 4-22-02

NO. 2002061681

Form CP-2/3

APR 15 2002

replacement card

RITCHIE EXPLORATION  
WICHITA KS 67202

4-12S-22W  
440'FSL & 2200'FWL, SEC

# 3 ADA OWWO

site: 2-1/2 N & 3/4 W OF OGALLAH KS

cty: TREGO

API 15-195-21732

cntr: UNKNOWN

field: RINKER EAST

geol:

fr date 05/01/95

spd date 06/27/94

drilg comp 06/27/94

card issued 05/01/95

last revised 02/05/96


ELV: 2400 KB, 2395 GL LOG	tops.....	depth/datum
ANH.....	1840	+ 560
B/ANH.....	1883	+ 517
TOP.....	3418	-1018
HEEB.....	3636	-1236
TOR.....	3656	-1256
LANS.....	3670	-1270
BKC.....	3909	-1509
MARM.....	4002	-1602
PBD.....	4086	-1686
RTD OLD.....	4095	-1695
LTD OLD.....	4099	-1699

IP status

OIL, P 15 BO & 7.5 BWPD, LKC 3671-3880 OA, MARM 4012-4022, CONG 4069-4072, (NEW PAY), 06/30/94  
 INFO REL: 2/5/96 - WAS OIL WELL - TIGHT HOLE  
 OLD INFO: OPERATOR WAS A SCOTT RITCHIE, 3 ADA, SPD 07/18/85, 07/26/85 8-5/8" 259 / 200 SX, 4-1/2" 4090 / 185 SX, OIL, P 28.35 BO & 11 BWPD, LKC 3671-3880 OA, MARM 4012-4022, (CARD ISSUED 12/05/85)  
 CONTR: MURFIN DRILLING  
 GEOL: BOB BUFFO  
 NO CORES

COPYRIGHT 1996  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

RITCHIE EXPLORATION  
WICHITA KS 67202

4-12S-22W  
440'FSL & 2200'FWL, SEC

# 3 ADA OWWO

DST (1) 3631-3702 (TOR, LANS), / 30-45-30-45, 240' GIP, REC 60' GSY OILY WCM, 180' GSY OILY WCM. ISIP 739# FSIP 729# IFP 70# -90# FFP 100# -110#  
 DST (2) 3695-3740 (LANS 35, 50), / 30-45-30-45, REC 210' MW, NSO ISIP 473# FSIP 432# IFP 72# -92# FFP 123# -123#  
 DST (3) 3741-3758 (LANS 70), / 30-45-30-45, 120' GIP, REC 20' OCM, 40' HOCM ISIP 699# FSIP 689# IFP 30# -30# FFP 40# -40#  
 DST (4) 3762-3771 (LANS 90), / 30-30-30-30, REC 900' SW, NSO ISIP 679# FSIP 679# IFP 50# -250# FFP 330# -420#  
 DST (5) 3802-3867 (LANS 140, 160, 180), / 30-30-30-30, REC REC 5' M, W/SPKS OIL ISIP 92# FSIP 82# IFP 51# -51# FFP 51# -51#  
 DST (6) 3867-3912 (LANS 200, 220), / 30-45-30-45, REC 20' M, W/SPKS OIL ISIP 936# FSIP 884# IFP 51# -51# FFP 51# -51#  
 DST (7) 4003-4035 (MARM), / 45-45-45-45, REC 10' OCMV ISIP 549# FSIP 509# IFP 40# -40# FFP 50# -50#  
 MICT - CO, PF (MARM) 4012-4022, W / 1 SPF, AC 400 GALS, SWB DWN, SO, PF (LKC) 3878-3880, W / 2 SPF, AC 500 GALS, SWB DWN, PF (LANS) 3671-3674.5, W / 2 SPF, AC 750 GALS, SWB DWN, GSO, POP, P 28.35 BO & 11 BWPD, 8/28/85, COMMINGLED  
 NEW INFO: FR 05/01/95, REWORKED 06/27/94 DC 06/27/94 MICT - CO, PB 4086 TD, PF (CONG) 4069-4072, W/3 SPF, AC AC 500 GAL (15% INS), SO, PF (LKC) 3749-3751, W/2 SPF, AC 500 GAL (15% NE), SO, TSTD OLD PFS (LKC 3671-3880 OA & MARM 4012-4022), NO NEW TRTMNT, SO, SET 2-3/8" TBG AT 4079, NO PKR, POP, P 15 BO & 7.5 BWPD, 6/30/94, COMMINGLED (NEW PAY - CONG OIL)